

Tender Notice No.....3.86

Date:-22.1.24/2024.

MAHAVIR CANCER SANSTHAN AND RESEARCH CENTER, PATNA

Detail Tender Notice

Sealed Quotation are invited for MRI Non magnetic Interior and electrical works (BOQ attached) at Mahavir cancer Sansthan, Patna. The Quotation Should reach within 5 days from the date of issue of NIT by courier/registered post or drop into the tender box (Room No.03)-A Block mentioning therein the terms and conditions addressed to the Director Mahavir Cancer Sansthan Phulwarisharif, Patna 801505. Tender Number Should be mention on top of the sealed envelope, Quotationer may be pre visit the site as per his convenience. The Sansthan reserves the right to reject any or all tenders without assigning any reason thereof.

B. G. 14
22/1/24

3

BOQ for Non Magnetic Interior and Electrical Works

| S.N. | Category | Description | Unit | Qty. | Rate (Rs.) | Amount (Rs.) |
|-----------------|-----------------|---|------|-------|------------|--------------|
| RF CABIN | | | | | | |
| 1. | Floor | 2mm Anti Static Flooring including Skirting ,copper strip and all fittings. | SFT | 330 | | |
| 2. | Wall Paneling | Interior Wall Paneling with 12mm Thick Ply Board Panel and High Glossy Lamination Pasting (Century) | SFT | 568 | | |
| 3. | False Ceiling | 600 X 600 mm Mineral Fiber False ceiling System laid all Aluminium Frame(Armstrong or Equivalent) | SFT | 304.5 | | |
| 4. | RF Door Framing | RF Door Frame Paneling with 12mm Thick Ply Board Panel & High Glossy Lamination Pasting | Nos. | 1 | | |
| 5. | Cable Tray | 600MM Aluminium Cable Tray above False Ceiling | RMT | LS | | |
| 6. | Filter Plate | Shutter for Filter Plate matching with RF Cabin Panel | LOT | 1 | | |
| 7. | Diffuser | Aluminium Diffuser with powder coated of size 512 X 200 mm | Nos. | 4 | | |
| 8. | SKY Light | Providing and Fixing SKY View Light | Nos. | 1 | | |

Ben
12/6/22

21.6.2024

BOQ for Non Magnetic Interior and Electrical Works

| | | | | | | |
|----------------------------|---------------------|--|------|------|--|--|
| 9. | Cove Ceiling | Cove Ceiling | RMT | 20.2 | | |
| 10. | Sky Frame | Providing & Fixing Wood with Ply Structure | SFT | 35 | | |
| CONSOLE ROOM | | | | | | |
| 11. | RF Window Framing | RF Window Paneling with 12mm thick Ply Board panel with High Glossy Lamination Pasting (Non Magnetic) | Nos. | 1 | | |
| 12. | WALL PANELLING | Interior Wall Paneling with 12mm thick ply board Paneling and High Glossy Lamination Pasting (Non Magnetic) | SFT | 350 | | |
| 13. | Vertical Cable Tray | Plywood Vertical Cable Tray with open able cover 100mm X 100mm cover will be finish with Glossy Lamination (Non Magnetic) | RMT | 350 | | |
| Technical Room | | | | | | |
| 14. | Cable Tray | 600mm Aluminum Cable Tray above False Ceiling(all fittings shall be non Magnetic) | RMT | 1800 | | |
| RF CABIN ELECTRICAL | | | | | | |

D. G. M.
22/6/24

BOQ for Non Magnetic Interior and Electrical Works

| | | | | | | |
|-----|-------------|--|------|----|--|--|
| 15. | Power Cable | Supply, Laying, Thumbling of 4 core 50 Sqmm Flexible Cu Cable from UPS I/O MCCB to 60Kva UPS Input Terminal. | RMT | 15 | | |
| 16. | Power Cable | Supply, Laying, Thumbling of 4 core 35 Sqmm Flexible Cu Cable from 60Kva UPS Output Terminal to UPS output MCCB. | RMT | 18 | | |
| 17. | Power Cable | Supply, Laying, Thumbling of 4 core 35 Sqmm Flexible Cu Cable from UPS output MCCB to MCCB of UPS output . | RMT | 18 | | |
| 18. | Power Cable | Supply, Laying, Thumbling of 4 core 35 Sqmm Flexible Cu Cable from MCCB of UPS output to C1-110 A Contactor . | RMT | 3 | | |
| 19. | Power Cable | Supply, Laying, Thumbling of 4 core 35 Sqmm Flexible Cu Cable from C1-110 A Contactor to Electronic Cabinet . | RMT | 60 | | |
| 20. | Lights | 20 Watt MRI compatible LED Lights with wiring Size 200mm Diameter | Nos. | 8 | | |
| 21. | Lights | 10 Watt MRI compatible LED Lights | Nos. | 12 | | |

D. S. Reddy
22/6/24

BOQ for Non Magnetic Interior and Electrical Works

| | | | | | | |
|--------------------------------|--------|--|------|----|--|--|
| | | with wiring Size 100mm Diameter | | | | |
| 22. | Lights | LED Strip Light for ceiling cove | RMT | 20 | | |
| 23. | Switch | 5/15 A power point with switch for service with complete wiring | Nos. | 6 | | |
| 24. | Switch | Emergency stop switch with full wiring from contactor panel to Gantry Room | Nos. | 1 | | |
| 25. | Switch | Switch board containing switch 7 Nos. and 1 power point with complete wiring | Nos. | 1 | | |
| CONSOLE ROOM ELECTRICAL | | | | | | |
| 26. | Switch | Emergency stop switch with full wiring from Contactor panel | Nos. | 1 | | |
| 27. | Switch | 5/15 A power point with switch for service with complete wiring | Nos. | 6 | | |
| 28. | Switch | Switch board containing switch 7 Nos. and 1 Power point with complete wiring | Nos. | 1 | | |
| WAITING ROOM | | | | | | |

Boq
12/6/24

BOQ for Non Magnetic Interior and Electrical Works

| | | | | | | |
|-----|---------------|---|-----|-----|--------------------|--|
| 29. | False Ceiling | 600 X 600 mm Mineral Fiber False ceiling System laid all Aluminium Frame(Armstrong or Equivalent) | SFT | 195 | | |
| 30. | Cove Ceiling | Cove Ceiling | RMT | 20 | | |
| | | | | | Total Amount-----> | |

P. K. Gupta
22/6/24